

BILL OF QUANTITY

कार्य का नाम - नगर निगम सीतामढ़ी अन्तर्गत वार्ड न०-35 में प्रमोद पासवान के घर से रोहिन पासवान के घर तक आर०सी०सी० नाला निर्माण कार्य।

NIT No. :
B.O.Q. Amount : 39,39,817.00

Cost of B.O.Q. :

Earnest Money : 78,800.00

Date of Receipt of Tender:

Time of Completion :

SL No	SOR NO.	ITEM OF WORK	QTY.	UNIT	RATE	AMOUNT
1	2.8.1	Earth work in excavation in foundation trenches or drains(not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m . including getting out the excavated soil and disposal of surplus excavated soil	334.49	Cum	360.70	120651.00
2	2.28	Supplying and Filling in plinth with local sand and under floors including, watering, ramming consolidating and dressing complete.	18.58	Cum	287.30	5338.00
3	11.72	Providing designation 100 A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/I,	243.96	Sqm	283.30	69114.00
4	4.1.3	Providing and laying in position cement concrete of specified grade excludng the cost of centring and shuttering-all work upto plinth level.1:2:4 (1cement :2coarse sand 4 graded stone aggregate 20 mm nominal size)	18.58	Cum	3998.10	74285.00
5	5.1.2	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement-All work puto plinth level1:1:5:3(1 cement: 1.5 coarse sand:3 graded stone aggregate 20 mm nominal size)	183.60	Cum	4688.30	860772.00
6	5.9	Centring and shuttering including strutting,propping etc. and removal of form for ...				
a	5.9.1	Centring and shuttering including strutting,propping etc. and removal of form for Foundations, footings, bases of columns etc. for mass concrete.	1545.72	Sqm	211.60	327074.00
b	5.9.3	Centring and shuttering including strutting, propping etc. and removal of form for Suspended floors, roots, landings, balconies and access plaltform	146.38	Sqm	437.50	64041.00
7	5.22.7	Supplying fitting placing TMT bar reinforcement (Fe 500) in substructure complete as per drawing and technical specifications clauses 1002,1005,1010 & 1202.	16209.38	Kg	92.60	1500989.00
8		Carriage of Material				
a		Bricks	7870.00	TH	1214.80	9561.00
b		Local Sand	22.24	M³	316.15	7031.00
c		Sone Sand	78.14	M³	3141.20	245453.00
d		Stone Aggt.	156.28	M³	2423.10	378682.00
e		Cement	73.52	MT	501.20	36848.00
9		Extra cost of Material				

	a	Bricks	7870.00	TH	369.30	2906.00
	b	Cement	73.52	bag	238.15	17509.00
10	8.2.2.1	Providing and Fixing of Granite shilapatt (2'0"x2'6") for Shilanyas/inauguration.	1.00	Each	4866.00	4866.00
					Total Rs	3725120.00
		Add- G.S.T @ 5.36%	3725120.00	%	5.36	199666.00
						3924786.00
11		Seinlorage Fee				
	a	Brick	7870.00	TH	512.80	4036.00
	b	Local Sand	22.24	M³	14.19	316.00
	c	Sone Sand	78.14	M³	17.58	1374.00
	d	Stone Aggt.	156.28	M³	59.54	9305.00
					Total	15031.00
					Total	3939817.00

Sme
17.12.24
nig

Nital
21/2/24

B.O. & Approved for Rs 39,39,817=00 (Rupees for thirty nine lacks thirty nine thousand eight hundred seventeen) only.

3200
21/02/24
कार्यपालक अभियंता
नगर विकास प्रमंडल
सीतामढी